

DIRECT VENT “START-UP” PROCEDURES

YOUR VERY FIRST FIRE SHOULD RUN **CONTINUOUSLY FOR 4 HOURS**. THIS CONTINUOUS BURN **WILL CAUSE SMOKING AND ODORS** DUE TO THE MANUFACTURING PROCESS. THIS CAN SET OFF SMOKE DETECTORS. **DO NOT BE ALARMED**. THIS HAPPENS ONLY DURING THIS CONTINUOUS 4 HOUR START UP. YOU MAY WANT TO OPEN WINDOWS DURING THIS INITIAL START-UP.

AFTER THE 4 HOUR **CONTINUOUS** BURN, TURN OFF THE FIREPLACE AND LET IT COOL COMPLETELY. REMOVE AND CLEAN THE GLASS. REPLACE THE GLASS AND RUN THE FIREPLACE **CONTINUOUSLY** FOR AN ADDITIONAL **6 HOURS**. THIS WILL COMPLETE THE START-UP PROCESS.

MOISTURE WILL OFTEN APPEAR ON THE GLASS FOR THE FIRST 2-4 MINUTES OF EACH USE. THIS IS NORMAL & WILL DISAPPEAR SHORTLY. IT WILL MAY BE NECESSARY TO CLEAN THE GLASS PERIODICALLY.

- WARNING -

CHILDREN AND ADULTS SHOULD BE ALERTED TO THE HAZARDS OF **HIGH SURFACE TEMPERATURES** OF THE GLASS & METAL SURROUNDING THE FIREPLACE.

THE AREA DIRECTLY ABOVE THE FIREPLACE CAN BECOME **EXTREMELY HOT**. PICTURES, MANTEL SHELVES, PLASMA TELEVISIONS ETC. ABOVE THE FIREPLACE CAN BE NEGATIVELY AFFECTED FROM THE HEAT. THIS CAN BE ALLEVIATED BY INSTALLING THE OPTIONAL CIRCULATING FAN (MUST BE PRE-WIRED WITH 120V AC).


DO NOT MOVE LOGS FROM THERE FIXED POSITION. BY DOING SO WILL CAUSE FLAME IMPINGEMENT & WILL CAUSE A CARBON BUILD UP. **NEVER** OPERATE WITHOUT THE GLASS PANEL.

PLEASE REFER TO THE “HOMEOWNER CARE & OPERATION” MANUAL FOR COMPLETE INFORMATION.

Gas Logs • Glass Doors • Mantels • Accessories
 Barbecues • Cultured Stone • Wood Stoves • Marble

Pre-Fab Fireplace Specialists

Visit our showroom

1-696	 N	Coolidge	(exit 14)	American Fireplace ★
9 Mile			Northend	
8 Mile				

Mon. - Fri. 9:00 - 5:00 • Sat. 10:00 - 3:00